

TOWN OF EAST WINDSOR ENGINEERING & PUBLIC WORKS

Mailing Address: 11 Rye Street, Broad Brook, CT 06016 Physical Address: 6 Woolam Road, East Windsor, CT 06088

Leonard J. Norton, P.E. - Director of Public Works/Town Engineer- Phone (860) 292-7073, Fax (860) 292-7072

RFP Documents - Wapping Road Bridge Over Ketch Brook - Bridge No. 04501

East Windsor, CT - March 16, 2015

East Windsor Request for Proposal

Proposals will be submitted to the Director of Public Works/Town Engineer, 11 Rye Street, Broad Brook, CT 06016, by 11:00am Friday, April 10, 2015. The project involves the repair of scaling and honeycombing on the wing walls, underdeck and fascia beam on the subject bridge. Work to be as noted in the Conn. DOT Bridge Safety Inspection Report dated October 22, 2014, copies attached.

INFORMATION FOR BIDDERS

Tax Exemption – Purchase of materials are exempt from Connecticut sales tax.

Site Inspection – Each proposer shall satisfy himself as to the nature and location of the work, the general and local conditions and all other matters which can in any way affect the work or the cost of successfully performing the work. A mandatory Pre-Bid site inspection will be conducted on Monday, March 30, 2015 at 9:00AM.

Proposal – Each proposer shall fill in all blank spaces of the PROPOSAL FORM in ink with no changes made to the form. Each bid must be in a sealed envelope addressed to the Director of Public Works/Town Engineer, 11 Rye Street, Broad Brook, CT 06016.

Right to Reject Proposals – The town reserves the right to reject any or all proposals if it is the Town's best interest to do so. Proposals submitted or received after the scheduled closing time for receipt of bids will be rejected.

Acceptance of Proposals – Acceptance of proposal will be by notice of the Town Engineer.

Performance Bond - Required

RFP FORM

The undersigned declares he has carefully examined the RFP Documents and location(s) of work for the above referenced project and proposes to perform the work at the following UNIT Prices:

Item No	Brief Description Of Work	Est Quant	Unit Price	Total Cost
1	Concrete repair of scaling and honeycombing	Lump Sum	\$	\$

TOTAL PROPOSAL = \$				
WRITTEN			DOLLAR	S
AND			CENTS	
It is understood that the Lump Sur	n will control any con	tract awarded b	pased on this prop	osal.
The above prices include the cost of cost of mobilization and demobilizany other work required to complete	zation, miscellaneous	clearing and gru	ubbing, protection	of items and
The time of completion for the pro	oject is 30 days from t	he Notice to Pro	oceed date.	
The undersigned certifies that he hinterest in responding to this RFP.	nas not colluded with	any individual c	or firm that has a o	competitive
Name of Firm:				
Mailing Address:	•			
Phone Number:				
Signature of Proposer:			Tiţle:	
Name and Title (typewritten):				· · · · · · · · · · · · · · · · · · ·

GENERAL CONDITIONS

<u>Site Investigation – The contractor shall thoroughly investigate the site of the work and acquaint himself</u> with all available information concerning the project. Failure to do so shall not relieve him from responsibility for properly estimating the difficulty or cost of successfully completing the project.

<u>Measurements</u> – The Contractor shall be responsible for any measurements.

<u>Protection of Material and Work</u> – The Contractor shall at all times protect and preserve all materials, supplies, equipment, property and completed work and he will be held responsible for any loss or damage by any cause including the elements.

<u>Insurance</u> – The Contractor shall have the required insurance which shall be maintained in force until all work performed on this project is completed. All policies shall hold harmless the Town of East Windsor and the Town and its agents shall be named additional insured. Each insurance certificate shall contain a statement by the insurance carrier not to cancel the policy except upon thirty – (30) days notice to the Town.

Schedule of Insurance:

Manufacturer's and Contractor's Liability:

Personal Injury Liability

\$1,000,000 Per Person

\$1,000,000 per occurrence

Property Damage

\$1,000,000 per occurrence

Automotive Liability:

Personal Injury

\$1,000,000 per person

\$1,000,000 per occurrence

Property Damage Liability

\$1,000,000 per occurrence

Town's Protective Liability:

Personal Injury Liability

\$1,000,000 per person

\$1,000,000 per occurrence

Property Damage Liability

\$1,000,000 per occurrence

The Contractor shall also carry Worker's Compensation Insurance as required by the State of Connecticut and any other applicable laws and regulations for all employees engaged in work under the Contract.

<u>Damages – The Contractor shall pay and make good repair to all losses or damages arising from any cause connected with the Contract, and shall indemnify and save harmless the Town from any and all liability and responsibility for any loss, damage or injury suffered in any way arising out of the Contract and shall defend any suit which may be brought against the Town or its agents, connected with the work under the Contract and shall pay all costs or arising out of the Contract.</u>

Extension of Time – If conditions beyond control of the Contractor occur and cause delay, the Contractor may request from the Town Engineer an extension of time, clearly stating the reason for such request. The Engineer may grant such an extension in writing; however, this shall not be deemed to relieve the Contractor from his responsibility under this contract.

<u>Measures to Protect the Public</u> – The Contractor shall provide and maintain warning signs, lights, signal devices and barricades at appropriate locations to warn the public of any damages associated with the project and to prevent access to dangerous areas and shall comply with reasonable requests of the Town Engineer for additional measures to protect the public.

<u>Clean Up</u> – Before the work is considered complete, the Contractor shall thoroughly clean all work areas, and remove all rubbish, debris, unused and surplus material resulting from the project, leaving the premises in a condition satisfactory to the Town Engineer. Any disturbed lawn areas shall be restored to as good or better condition to that existing before the project. If the lawn restoration is done late in the year the Contractor shall be required to complete the work to establish an acceptable lawn in Spring of the following year.

<u>Inspection</u> – All materials and workmanship shall be subject to inspection by the Town Engineer or his representative at any time during storage on-site or construction. The Town has the right to reject defective material and workmanship or require its correction. Rejected workmanship shall be satisfactorily corrected while rejected materials shall be promptly removed from the site.

<u>Changes in Contract Documents, Scope of Work</u> – The Town Engineer reserves the right to make changes to the contract documents or change the scope of work at any time before or during the project.

<u>Commencement, Prosecution and Completion</u>—The Contractor shall start work under this contract within 7 days of the Notice to Proceed date, and he shall prosecute the work faithfully to completion, including final clean-up, within the specified time project.

<u>Payments</u> – For a contract under 60 day's duration, payment shall be made within 30 days of completion of the work. For a contract of 60 days duration or more, partial payments shall be made within 30 days of the receipt of a certified estimate of work performed during the month, approved by the Town Engineer.

Retainage — a 10% retainage shall be held from payments made to the Contractor if there is work remaining such as lawn restoration, which cannot be completed due to the season.

SPECIAL CONDITIONS

Time for Completion – 30 days starting from the Notice to Proceed.

Permits – Not required

Work on Private Property, Easements - N/A

Subsurface Information - None available.

CONSTRUCTION REQUIREMENTS

<u>General</u> – It is the Town's intent to secure work which, at a minimum, will meet the requirements of Conn DOT "Standard Specifications for Roads, Bridges and Incidental Construction, Form 816, 2004".

STRUCTURE NO. 04501

WAPPING ROAD over KETCH BROOK EAST WINDSOR

JX 12/15/14
Rechark srow

Ratins.

1996 Scorr Report has

Hen 113-3

Rodine, Special & Underwater Inspection

on 10/22/2014

Inspected by Collins - 52 for Area 3

TEAM:	Forwarded to TE3. Amy Stula	Dale	12/4/2014
<u>TE3:</u>	Reviewed by TE3 Army Stula	Date \	2-11-14
	BMM Regulred	No	
	Town Bridge	Nes	
	Rating <= 5 (items 58,59,60 or 62)	No	
	Rating Change 2 or More Values	100	n in the second
	Forwarded to Supervisor, Share Keedy	Date 12-17	<u> </u>
	Forwarded to "To Be Copled Drawer"	Dale	And the second s
· · · ·	Date BRI-19 Entered 12-11-1	4	12 es 12 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
SUPERVI	SOR: Reviewed by Supervisor	Date	
SUPPOR	T: Date Copies Made	Dien Lall	oj. da on
	Scanned By: Date Scanned	POF	Box No

NBI: Yes


NHS: No



CONNECTICUT DEPARTMENT OF TRANSPORTATION

STATE PROJECT NO. 170-3163
BRIDGE SAFETY INSPECTION

BRIDGE NO. 04501
WAPPING ROAD
OVER
KETCH BROOK
EAST WINDSOR, CONNECTICUT



ROUTINE & UNDERWATER INSPECTION OCTOBER 22, 2014



Prepared By:

COLLINS ENGINEERS 2 101 HAMMER MILL ROAD ROCKY HILL, CT 06067 Garg Consuling Services, Inc.

2096A SILAS DEANE HWY ROCKY HILL, CT 06067

rapy processing successing in the processing and in-	samaan saasi saleen daraa saadada saasi sa	esterijas assaulja os armatinis ir ir internasioni or armati ir armatiligija i distributionis aidilistikai est 	omanife (h. N. N. S.
			•••
59. SUPERSTRUCTURI	Reinforced Cond	crete Frame.	Overall Rating: 6
	Rating		
BEARING DEVICES	: N	-	
STRINGERS	: N	See 'Girders' Item.	
GIRDERS	6	The underside of the concrete frame has up to full length honeycombing with efforescence and hairline map cracintermittent light honeycombing throughout. The west fax 3" deep scale. Both fasclas have full length x 18" high honeycombing up to ½" deep. The overall concrete deterioration at the underside of the See Sheet 13 & 14 and Photos 9, 12 & 13.	ks along both fascias and scia has full length x 1' high hairline map cracking and
EL COR REALIC		See Sheet 13 & 14 and 1 holds of 12 & 10.	
FLOOR BEAMS: TRUSSES-GENERAL			
TRUSSES-PORTALS			
TRUSSES-BRACING			
PAINT		<u> </u>	
RUST		_	
MACHINERY MOV	N	-	
RIVETS & BOLTS:		-	
WELDS - CRACKS:	N		
TIMBER DECAY:	N .	_	
CONCRETE CRACKING:		See 'Girders' item.	
COLLISION DAMAGE:		-	
MEMBER ALIGNMENT:	8	-	
DEFLECT. UNDER LOAD:	N	(N) Normal (E) Excessive	
VIBRATION UNDER LOAD:	N	(N) Normal (E) Excessive	
STAND PIPES:	N	-	
BARREL LADDERS:	N	<u>- </u>	OUL COMPLIANTONA
		ARE BARREL LADDERS C	OSHA COMPLIANI? NA
60. SUBSTRUCTURE:	The bridge was refundermining along	te Frame legs with wingwalls. nabilitated in December 2006. This work addressed both abutments with exposed and corroded steel riprap and a stepped footing.	Overall Rating:

Rating

		The first transfer of the second seco
ABUTMENTS-STE	/ i: 6	Both frame legs above the step footing exhibit random honeycombing up to 1" deep and concrete patches. The South Abutment has halfiline cracks with efflorescence,
		See Sheets 17 & 18 and Photo 14 & 15.
ABUTMENTS BACKWALI		র ব্যক্তিক স্থানিক সামি সঞ্জানিক ক্রমি আমি সামিল্লক করা সামি করা সামিল সামিল করা করা করা বিবাহ করা সামিল করা স সমস্ক্রিক স্থান সামিল করা সামিল করা সামিল স
ABUTMENTS FOOTINGS) - 7	Both Abutment stems are founded on 7-steel H-Piles spaced approximately 5-feet on center. Stepped footings and riprap were placed to repair the undermining noted in the 2006 inspection.
· · · · · · · · · · · · · · · · · · ·	, , , , , , , , , , , , , , , , , , , ,	See Sheets 17 & 18,
ABUTMENTS SETTLEMENT	:	
ABUTMENTS WINGWALLS		The wingwalls are not founded on steel H-piles. All of the wingwalls exhibit map cracking, efflorescence, and honeycombing up to 1/2" deep along the face. The Southwest Wingwall has an edge spall (2.5' long x 6" wide x 6" high) along the top and scaling (up to 5' long x full width x 1" deep)along the top. The Southeast Wingwall exhibits scale (up to 2" deep x full length x full width) along the top that extends down the faces up to 6" with exposed rebar. The Northeast Wingwall has scale (6' long x full width x up to 2.5" deep) along the top that extends down the face up to 1'. Adjacent to the scale is two spalls up to 2' long x up to 8" wide x 5" deep with exposed rebar. The Northwest Wingwall has an edge spall (1.2' long x 5" wide x 2" deep) along the top and scale (4' long x 6" wide x 1.5" deep) along the lop.
		See Sheets 17 & 18 and Photos 16-19.
PIERS/BENTS-CAPS		
PIERS/BENTS-PILE		
PIERS/BENTS- COLUMNS:	N .	
PIERS/BENTS- FOOTING:		
PIERS/BENTS- SETTLMT:		
EROSION-SCOUR:		Riprap up to 1.5' diameter is in place along both abutments and is covered with concrete overpour from the step footings. Mudline elevations remain relatively unchanged (+/-0.5') along the abutments since the 2010 Inspection. There is an isolated area of degradation up to 1.2' at the west end of the North Abutment. The elevations could not be compared to the 2012 Inspection due to Incomplete soundings taken during the 2012 Inspection. See Sheets 15-18.
CONCRETE CRACK- SPALL:	6	See 'Abutments-Stem' & 'Abutments-Wingwalls' Items.
STEEL CORROSION:	6	No Steel Corrosion was observed due to the rip rap and concrete overpour at the footings which has covered the steel H-piles. Rating based on previous rating.
PAINT:	N	The Killings of Walker Company of the Wall Company of the Company
TIMBER DECAY:	N .	
COLLISION DAMAGE:		
DEBRIŠ:	N	

Bridge No.	04501	Inspected hy.	O O
Town:	East Windsor	Inspected by:	C. Perry (Collins)
Feature Carried:	Wapping Road	Date Inspected:	J. Figueroa (Collins), C. Sorensen (Garg)
Feature Crossed:	Ketch Brook	Project No.:	170-3163
	10.22.2014		
Photo # 9: Undersi	Photo # 9: Underside of Deck, Looking Northeast	Photo # 10: West	Photo # 10: West Bridge Rail, Looking Southwest
		2	



Bridge No. 04501 Town: East Windsor Feature Carried: Wapping Road Feature Crossed: Ketch Brook Project Read Retch Brook Project Retch Bridge Rail, Looking Southeast Photo # 11: East Bridge Rail, Looking Southeast Note	Inspected by:		Date Inspected: 10/22/2014		10.22.2014	Photo # 12: West Fascia, Looking Northeast	Note: Delamination and spall up to 1' high x 3" deep	
		East Windsor	Wapping Road	Ketch Brook			Not	



outh A	Bridge No.	04501	Increased by:	
# 13: Underside of Deck at West Fascia, Looking adjacent to delamination and spalls on	Town:	East Windsor	Inspected by:	C. Perry (Collins)
Project No.: Project No.: Photo # 14: South A	Feature Carried.	Wanning Dood	Inspected by:	J. Figueroa (Collins), C. Sorensen (Gard)
Project No.: 170-3163 Photo # 14: South Abutment, Looking Southwe	Footing Crossel.	wapping Road	Date Inspected:	10/22/2014
Photo # 14: South Abutment, Looking Southwe	r carar e olossed:	Neich Brook	Project No.:	170-3163
Photo # 14: South Abutment, Looking Southwe	がはない。		,	
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe			146	
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe	(4)			
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe				
Photo # 14: South Abutment, Looking Southwe	一	10 22 2044	\ \	•
		# 107 M		10.22.2014
	Photo # 13: Under	side of Deck at West Fascia, Looking	Photo # 14: South	Abutment Looking Southers
Note: Map cracking adjacent to delamination and spalls on fascia.				Seaming Southwest
	Note: Map crackin fascia.	g adjacent to delamination and spalls on		



Dorn't Collico	J. Figueroa (Collins). C. Sorensen (Gara)	10/22/2014	170-3163	Photo # 16: Southwest Wingwall, Looking South	
Inspected by:	Inspected by:	Date Inspected:	Project No.:	Photo # 16: Sour	
Bridge No. 04501		Feature Crossed: Wapping Road	regule Clossed: Netch Brook	Photo # 15: North Abutment, Looking Northwest	



Bridge No.	04501	Increated by	
Town:	East Windsor	Inspected by.	C. rerry (Collins)
Feature Carried:	Wapping Road	Dafe Inchested	J. Figueroa (Collins), C. Sorensen (Garg)
Feature Crossed:	Ketch Brook	Project No.	170-3163
		2000	2017-0-1
	10 22.2011		700.7
Photo # 17: Southe	Photo # 17: Southeast Wingwall, Looking East	Photo # 18: North	Photo # 18: Northwest Wingwall, Looking North
Note: Scale with ex wingwall.	Note: Scale with exposed rebar along the top of the wingwall.	Note: Scale along top of wingwall.	top of wingwall.



Inspected by: C. Perry (Collins)		ż		Project No.: 170-3163	_	ed:	Inspected by: J. Figueroa (Collins), C. Sorensen (Gard)		Inspected by: C. Perry (Collins)
04501		Wapping Road	d: Ketch Brook		-	+	t	East Windsor	10000
Bridge No.	I OWn:	Feature Carried:	Feature Crossed:	realure Crossed.	Tuesda o mana	Feature Crossed:	Ecoderyo Courted.	Town:	Town.

