

TOWN OF EAST WINDSOR  
DRAINAGE IMPROVEMENT  
79 TROMLEY RD.

**ADDENDUM #1**  
**May 1, 2024**

Question: This entire project is off to the side of the road correct?

Answer: Refer to plan

Question: Is the trees that need to be removed in plans by other? Or by contractor?

Answer: Tree's have been removed. Stumps are the responsibility of the contractor.

Question: What are your thoughts on traffic control? Is this something that should be included in the bid, or will the Town supply?

Answer: Traffic control supplied by contractor.

Question: Is the project tax exempt?

Answer: Yes.

Question: Will bonding be required? Bid, performance, payment?

Answer: Performance and payment bonds are required.

Question: Is the project prevailing wage?

Answer: No.

Question: What will the Town want for temporary patch? Thickness of it?

Answer: 2" class 2 HMA.

Question: When is the project planned to start?

Answer: ASAP

CPEP-S TRENCH DETAIL REVISION:

Continue ¾" crushed stone to top of pipe.